

Service

BULLETIN #147

MARCH 2000

PAGE 1/1

MODELS AFFECTED


P-80

SUBJECT

**REVISED HOUSING HOLD-DOWN CAP SCREWS
AND NUT TORQUE**

The housing hold-down cap screw torque values have been increased to 136 N•m (100 lbs. ft.) from 101-116 N•m (75-86 lbs. ft.).

The P-80 installation manual procedure requires torquing the cap screws in the sequence below, first to 55 N•m (40 lbs. ft.) then to 101-116 N•m (75-86 lbs. ft.) The sequence below and in the manual are correct, only the final torque has been changed (increased to 136 N•m (100 lbs. ft.)) Please make the necessary changes to any installation manuals you have for reference purposes.



Product improvement not subject to campaign.

Pacbrake Service

PACBRAKE[®]
ENGINE & EXHAUST BRAKES

Phone: 800-663-0096 • Fax: 604-882-9278 • E-mail: info@pacbrake.com • Internet: www.pacbrake.com
Canada: 19594 - 96 Ave., Surrey, BC V4N 4C3 • USA: P.O. Box 1822, 250 H St, Blaine, WA 98231-1822